
IH-767 PROPOSED SUBDIVISION PLAN ISSUED MARCH

PROPOSED SUBDIVISION PLAN ONE HOME BUILDERS, LLC TAX MAP 2, LOT 20


LOCATION MAP

CIVIL ENGINEERS:






LAND SURVEYORS:





CAREX ECOSCIENCES
2 WASHINGTON STREET
DOVER,NH 03820
1-603-742-6665



DRILL HOLE

PINES, ETC.

MAPLES, ETC.

EXIST. SPOT GRADE

PROP. SPOT GRADE

DOUBLE POST SIGN SINGLE POST SIGN

EXISTING LIGHT POLE

EXISTING CATCH BASIN PROPOSED CATCH BASIN

RTE 9 RTE 9 ROAD LONG HILL RD RESERVOIR

MADBURY N.H. NOT TO SCALE

PLAN SET LEGEND

•	OVERHEAD ELEC. LINE	
•	FENCING	X
0	DRAINAGE LINE	——D ———D ——
₽.	SEWER LINE	<u> </u>
©	GAS LINE	G
ф	WATER LINE	
	STONE WALL	-
	TREE LINE	. ~~~
**	ABUT. PROPERTY LINES	
EG 3	EXIST. PROPERTY LINES	
96×69	BUILDING SETBACK LINES	
96x69	EXIST. CONTOUR	
	PROP. CONTOUR	
	SOIL LINES	

<u>INDEX</u>

TITLE SHEET

- 1 EXISTING CONDITIONS PLAN
- 2 SUBDIVISION PLAN
- 3 SUBDIVISION SITE PLAN
- 4 P1 PLAN AND PROFILE (HUCKINS)
- 5 P2 PLAN AND PROFILE (PROPOSED ROAD)
- 6 X1 CROSS SECTTIONS (HUCKINS)
- 7 X2 CROSS SECTIONS (PROPOSED ROAD)
- 8 X3 CROSS SECTIONS (PROPOSED ROAD)
- 9 CONSTRUCTION DETAIL SHEET
- 10 EROSION CONTROL DETAILS

RECORD OWNER:

LOUISE ABBOTT
38 HUCKINS ROAD
MADBURY, NH 03823


APPLICANT:


ONE HOME BUILDERS, LLC PO BOX 334 STRAHAM, NH 03885


REQUIRED PERMITS


NHDES SUBDIVISION APPROVAL NUMBER
NPDES APPROVAL NUMBER:

REVISIONS:	DATE:









HOST PORT CLEY = 198.96
HIGH PORT ST = -04-239
PM ST = -04-239
PM ST = -100

K = 2.00

125.0000' VC

125.0000' VC

126.0000 VC

127.0000 VC

128.0000 VC

129.0000 VC

120.0000 VC

120.000


PROFILE SCALES:
HORIZONTAL: 1"=40' VERTICAL: 1"=4'

PREPARED FOR:

ONE HOME BUILDERS, LLC PO BOX 334 STRATHAM, N.H. 03885

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863




CONSTRUCTION NOTES

1. SILTATION/ EROSION CONTROLS SHALL BE INSTALLED PRIOR TO CONSTRUCTION, SHALL BE MAINTAINED DURING CONSTRUCTION, AND SHALL REMAIN UNTIL SITE HAS BEEN STABILIZED WITH PERMANENT VEGETATION. SEE DETAIL SHEET FOR ADDITIONAL NOTES ON EROSION CONTROL.

- 2. ALL DISTURBED AREAS NOT TO FINAL GRADE BY MID-NOVEMBER SHALL BE SEEDED WITH WINTER RYE OR ACCEPTABLE SUBSTITUTE AND MULCHED TO PROVIDE VEGETATION COVER.
- 3. FINAL DRAINAGE, GRADING AND EROSION PROTECTION MEASURES SHALL CONFORM TO REGULATIONS OF THE SUBDIVISION REGULATIONS.
- 4. ALL ROAD AND DRAINAGE WORK TO BE DONE IN CONFORMANCE WITH TOWN REGULATIONS AND NHDOT SPECIFICATIONS, WHICHEVER IS MORE STRINGENT.
- 5. CONTRACTOR TO VERIFY EXISTING UTILITIES AND TO NOTIFY ENGINEER OF ANY DISCREPANCY IMMEDIATELY.
- 6. ALL UTILITIES SHALL BE INSTALLED UNDERGROUND IN ACCORDANCE WITH REGULATIONS AND SPECIFICATIONS AS APPROVED BY THE APPROPRIATE UTILITY COMPANY. LOW PROFILE STRUCTURES SHALL BE USED TO THE GREATEST EXTENT POSSIBLE.
- 7. ALL BENCHMARKS AND TOPOGRAPHY SHOULD BE FIELD VERIFIED BY THE CONTRACTOR. ENGINEER TO BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY.

HUCKINS ROAD





REVISIONS: DATE:

P1 PLAN AND PROFILE

PLAN FOR:
RESIDENTIAL DEVELOPMENT
LONG HILL ROAD
MADBURY, NH

DATE: MARCH, 2014	SCALE: AS SHOWN	
PROJ. N0: NH-767	SHEET NO. 4 OF 10	





ONE HOME BUILDERS, LLC PO BOX 334 STRATHAM, N.H. 03885

BEALS · ASSOCIATES PLLC


70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863


<u></u>			
			DATE:


X1 CROSS SECTIONS

PLAN FOR: RESIDENTIAL DEVELOPMENT LONG HILL ROAD MADBURY, NH


DATE: MARCH, 2014	SCALE: AS SHOWN
PROJ. N0: NH-767	SHEET NO. 6 OF 10








- 1. CONSTRUCT THE LEVEL SPREADER LIP ON A 0% GRADE TO INSURE UNIFORM SPREADING OF RUNOFF.
- 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.
- 3. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING EXCELSIOR ENFORCER MATTING BENEATH THE STONE. EACH STRIP SHALL OVERLAP BY AT LEAST SIX INCHES.
- 4. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 5. MAINTENANCE: THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND THE DESIGN CONDITIONS HAVE NOT CHANGED. ANY DETRIMENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED. IF STONE REMOVAL HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED.




UTILITY TRENCH DETAIL




F	PART No.	PIPE SIZE	A	B(MAX)	Н	L	w
	1510-NP	15" 375 mm	6.5" 165 mm	10" 254 mm	6.5" 165 mm	25" 635 mm	29" 735 mm
	1810-NP	18 * 450 mm	7.5 " 190 mm	15" 380 mm	6.5 " 165 mm	32" 812 mm	35" 890 mm
2	2410-NP	24" 600 mm	7.5" 190 mm	18" 450 mm	6.5" 165 mm	36" 900 mm	45" 1140 mm
,	3010-NP	30 " 750 mm	10.5" 266 mm	N/A	7.0" 178 mm	53" 1345 mm	68 * 1725 mm
	3610-NP	36" 900 mm	10.5" 266 mm	N/A	7.0" 178 mm	53" 1345 mm	68" 1725 mm

PE THREADED ROD W/ WING NUTS PROVIDED FOR END SECTIONS 15"-24". 30" & 36" END SECTIONS TO BE WELDED PER MANUFACTURER'S RECOMMENDATIONS.

ADS N-12 FLARED END SECTIONS NOT TO SCALE (ALL DIMENSIONS ARE NOMINAL)



-5/16" MACHINE SCREW OR BOLT STREET SIGN DETAIL



TYPICAL ROADWAY CROSS SECTION NOT TO SCALE

NOTE: GEOTEXTILE FABRIC

OR FILTER MATERIAL TO BE PLACED BETWEEN RIP RAP AND SOIL.

1. THE SUB GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED

2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO THE SPECIFIED GRADATION.

3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF

5. STONE FOR RIRAP SHALL BE ANGULAR OR SUBANGULAR. THE STONES SHOULD BE SHAPED SO THAT

6. FLAT ROCKS SHALL NOT USED FOR RIP RAP. VOIDS IN THE ROCK RIPRAP SHOULD BE FILLED WITH

1. THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM.

EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS

TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL

THE ROCK RIP RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF

FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS

REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.

4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED

TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT

IF THE RIP RAP HAS BEEN DISPLACED, UNDERMINED OR DAMAGED, IT SHOULD BE REPAIRED IMMEDIATELY. THE CHANNEL IMMEDIATELY BELOW THE OUTLET SHOULD BE CHECKED TO SEE THAT

SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR

THE LEAST DIMENSION OF THE STONE FRAGMENT SHALL BE NOT LESS THAN ONE-THIRD OF THE

PIPE OUTLET TO WELL-DEFINED CHANNEL

FILL MATERIAL FOR EMBANKMENT SHALL BE TAKEN


FROM APPROVED BORROW AREAS. IT SHALL BE

CLEAN MINERAL SOIL FREE OF ROOTS, ORGANIC MATTER, AND OTHER DELETERIOUS SUBSTANCES. IT TOP OF BERM SHALL CONTAIN NO ROCKS OR LUMPS OVER (6) INCHES IN DIMENSION, AND NOT MORE THAN LEVEL WOODEN CONTROL FIFTEEN PERCENT (15%) OF THE ROCKS OR LUMPS SHALL BE GREATER THAN 2 1/2 INCHES OR LESS -RIP RAP SPILLWAY AND BE COMPACTED TO AT LEAST 90% OF ASTM D-1557. FILL MATERIAL SHALL MEET NHDOT ITEM RIP OUTLET APRON 304.2: 6" PASSING 100%, #4 SIEVE 70-100%, #200 SIEVE 0-12%. OUTLET FLARED END -ANTI-SEEP-LFLARED END SECTION COLLARS SECTION

STOP SIGN (R1-1) 30" x 30"

SPEED LIMIT SIGN (R2-1) 24" x 30"

DETENTION POND BERM & OUTLET DETAIL



SEED ALL SLOPES WITH BLUE SEAL SCS CONSERVATION MIX AT 2 lbs./1000 S.F. ENTRY CHANNEL 6" DIA. INLET PROTECTION 6" DIA. PERFORATED RISERS RISERS STONE LS SEE DETAIL SHEET (EXTEND UP 3:1 SLOPE) /ELEV 107.25' PERFORATED BERM TRAP. 2' DIA. ONLY IN WEIR PERFORATED 6" DIA. RISER STONE BERM STONE L = 8', RISER W/OPEN PERFORATED IN STONE LEVEL SPREADER LAYER. ELEV ELEV. 170.00 ELEV. = GRATE. ÉLEV, LAYER ONLY ELEV. 169.75' 166.75' 167.50 W/CLEAN-OUT(TYP). = 169.0'8" WETLAND SOIL ENTRY CULVERT 3" PEA STONE BETWEEN LEV. 168.0' SURFACE ELEV. = WETLAND SOIL AND **EXISTING GRADE** STONE (TYP.) ESHWT = TP A-2(-68" OR EL 160 NONE) **UNDERDRAIN** 24" OF 3/4" STONE 20'x6" ADS CULV. 6" UNDERDRAIN TO 15" FOREBAY ELEV. 166.0 (TYP) LAID LEVEL. ELEV RISER AND 15" OUTLET CULVERT (SEE INSET). 22'x15" ADS CULV. LAID LEVEL. ELEV SECTION OF GRAVEL WETLAND = 163.33' NOT TO SCALE

SECTION A-A

CONSTRUCTION SPECIFICATIONS

SEGREGATION OF THE STONE SIZES.

SPALLS AND SMALLER ROCKS.

DAMAGE TO OUTLET PROTECTION.

MAINTENANCE

GREATEST DIMENSION OF THE FRAGMENT.

PIPE OUTLET TO FLAT AREA

WITH NO DEFINED CHANNEL


TO THE LINES AND GRADES SHOWN ON THE PLANS.

PREPARED FOR:

ONE HOME BUILDERS, LLC PO BOX 334 STRATHAM, N.H. 03885

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



1. PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL CONFORM TO STREET OPENING REGULATIONS. 2. NEW ROADWAY CONSTRUCTION SHALL CONFORM TO SUBDIVISION

TYPICAL DRAINAGE TRENCH

NOT TO SCALE

CONSTRUCTION CRITERIA

DN: ARFA SHALL RE CLEARED OF TREES LOGS. STUMPS ROOTS, BRUSH, BOULDERS, SOD AND RUBBISH. SUBGRADE SURFACE TO BE ROLLED BEFORE PLACEMENT OF FILL MATERIAL. THE SURFACE SHALL HAVE MOISTURE ADDED OR IT SHALL BE COMPACTED IF NECESSARY SO THAT THE FIRST LAYER OF FILL MATERIAL CAN BE COMPACTED AND BONDED TO THE SUBBASE

FILL PLACEMENT: FILL SHALL BE FREE OF SOD, ROOTS, FROZEN SOIL, STONES MORE THAN 6 INCHES IN DIA., AND OTHER OBJECTIONABLE MATERIAL.

-FILL TO PLACED EQUALLY AROUND SUBSURFACE STRUCTURES & PIPES TO PREVENT DAMAGE FROM UNEQUAL LOADING. -PLACING AND SPREADING OF FILL MATERIAL SHALL BE STARTED AT SUBGRADXE ELEVATION AND BROUGHT UP IN HORIZONTAL LAYERS OF THICKNESS' ALLOWING ADEQUATE COMPACTION. -DISTRIBUTION AND GRADATION OF MATERIALS SHALL BE SUCH THAT NO LENSES, POCKETS, STREAKS, OR LAYERS OF MATERIAL DIFFER SUBSTANTIALLY IN TEXTURE OF GRADATION FROM SURROUNDING MATERIAL -MAXIMUM THICKNESS OF GRAVEL LIFTS TO 1 FOOT (12 INCHES).


MOISTURE CONTROL: MOISTURE CONTENT OF THE FILL SHALL BE ADEQUATE FOR OBTAINING THE REQUIRED COMPACTION. IF THE MATERIAL IS TOO WET IT SHALL BE DRIED TO MEET THIS REQUIREMENT, IF THE MATERIAL IS TOO DRY IT SHALL HAVE WATER ADDED AND MIXED UNTIL REQUIREMENT IS MET.

COMPACTION: CONSTRUCTION EQUIPMENT SHALL BE OPERATED OVER THE AREAS OR EACH LAYER OF FILL TO INSURE THAT THE REQUIRED COMPACTION IS -EACH LAYER SHALL BE COMPACTED TO OBTAIN 95% OF THE PROTOR VALUE (ASTM 1557 OR AASHTO T180).

-FILL ADJACENT TO STRUCTURES, PIPES, ETC SHALL BE COMPACTED TO A DENSITY EQUIVALENT TO THAT OF THE SURROUNDING FILL BY THE MEANS OF

HAND TAMPERING OR MANUALLY DIRECTED POWER TAMPER OR PLATE VIBRATORS.


EROSION PROTECTION: A PROTECTIVE COVER OF VEGETATION SHALL BE ESTABLISHED ON ALL EXPOSED SURFACES OF THE EMBANKMENT (CUT/FILL)SLOPE, SPILLWAY, AND BORROW AREA IF SOIL AND CLIMATIC CONDITIONS PERMIT. IF CONDITIONS PRECLUDE THE USE OF VEGETATION AND PROTECTION IS NEEDED, NON-VEGETATION MEANS, SUCH AS EROSION BLANKETS OR RIPRAP SLOPE PROTECTION, MAY BE USED. -SEEDING, FERTILIZING, AND MULCHING SHALL COMPLY WITH THE APPROPRIATE VEGETATIVE BMP'S.



CONSTRUCTION DETAILS

PLAN FOR: RESIDENTIAL DEVELOPMENT LONG HILL ROAD MADBURY, NH

DATE: MARCH, 2014	SCALE: NTS	
PROJ. N0: NH-767	SHEET NO. 9 OF 10	



TEMPURARY ERUSION CONTROL MEASURES

1. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT NO MORE THAN 5 ACRES OF LAND SHALL BE EXPOSED BEFORE DISTURBED AREAS ARE

2. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED OR DIRECTED BY THE ENGINEER ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. 3. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN 1.10 POUNDS OF SEED PER 1000 SQUARE FEET OF AREA. (48 POUNDS PER ACRE) SEE SEED SPECIFICATIONS THIS SHEET. 4. SILT FENCES AND OTHER EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND

AFTER EVERY RAIN EVENT GREATER THAN 0.5" DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF. 5. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION

CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VEGETATED. 6. AREAS MUST BE SEEDED AND MULCHED WITHIN 3 DAYS OF FINAL GRADING,

PERMANENTLY STABILIZED WITHIN 15 DAYS OF FINAL GRADING, OR TEMPORARILY STABILIZED WITHIN 30 DAYS OF INITIAL DISTURBANCE OF SOIL. * AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

- BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE

- A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED.

- A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS RIPRAP HAS BEEN INSTALLED.

- EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

CONSTRUCTION SPECIFICATIONS

STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING.

2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION AND AIR AND WATER POLLUTION WILL BE MINIMIZED.

3. WHEN HAY BALES ARE USED, THE BALES SHALL BE EMBEDDED AT LEAST 4 INCHES INTO THE SOIL. WHEN TIMBER STRUCTURES ARE USED. THE TIMBER SHALL EXTEND AT LEAST 18" INTO THE SOIL.

4. HAY OR STRAW BALES SHALL BE ANCHORED INTO THE SOIL USING 2" X 2" STAKES DRIVEN THROUGH THE BALES AND AT LEAST 18 INCHES IN TO THE SOIL.

5. SEEDING, FERTILIZING, AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATED VEGETATIVE BMP.

6. STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS BEEN COMPLETED.

7. THROUGHOUT THE DURATION OF CONSTRUCTION ACTIVITIES THE CONTRACTOR SHALL TAKE PRECAUTIONS IN ORDER TO PREVENT, ABATE AND CONTROL THE EMISSION OF FUGITIVE DUST INCLUDING BUT NOT LIMITED TO WETTING, COVERING, SHIELDING, OR VACUUMING.

8. THE NH COMMISSIONER OF AGRICULTURE PROHIBITS THE COLLECTION, POSSESSION, IMPORTATION: TRANSPORTATION, SALE, PROPAGATION, TRANSPLANTATION, OR CULTIVATION OF PLANTS BANNED BY NH LAW RSA 430:53 AND NH CODE ADMINISTRATIVE RULES AGR 3800. THE PROJECT SHALL MEET ALL REQUIREMENTS AND THE INTENT OF RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES.

CONSTRUCTION SEQUENCE

1. CUT AND REMOVE TREES IN CONSTRUCTION AREAS AS REQUIRED OR DIRECTED. 2. CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMENT EROSION AND DETENTION CONTROL FACILITIES AS REQUIRED. EROŚION, SEDIMENT AND DETENTION CONTROL FACILITIES SHALL BE INSTALLED AND STABILIZED PRIOR TO ANY EARTH MOVING OPERATION AND PRIOR TO DIRECTING RUNOFF TO THEM.

3. CLEAR, CUT, GRUB AND DISPOSE OF DEBRIS IN APPROVED FACILITIES. STUMPS AND DEBRIS ARE TO BE REMOVED FROM SITE AND DISPOSED OF PER STATE AND LOCAL REGULATIONS. 4. EXCAVATE AND STOCKPILE TOPSOIL /LOAM. ALL AREAS SHALL BE STABILIZED IMMEDIATELY AFTER GRADING.

5. CONSTRUCT TEMPORARY CULVERTS AS REQUIRED OR DIRECTED. 6. CONSTRUCT THE ROADWAY/DRIVEWAYS AND ITS ASSOCIATED DRAINAGE STRUCTURES. ALL ROADWAYS, PARKING

AREAS. AND CUT/FILL SLOPES SHALL BE STABILIZED AND/OR LOAMED AND SEEDED WITHIN 72-HOURS OF ACHIEVING FINISH GRADE AS APPLICABLE. 7. INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. ALL DISTURBED AREAS


SHALL STABILIZED IMMEDIATELY AFTER GRADING. 8. BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AS REQUIRED, OR DIRECTED.

9. DAILY OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINAGE CHECK DAMS, DITCHES, SEDIMENT TRAPS, ETC. TO PREVENT EROSION ON THE SITE AND PREVENT ANY SILTATION OF ABUTTING WATERS OR PROPERTY. 10. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION

11. COMPLETE PERMANENT SEEDING AND LANDSCAPING 12. REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND

SITE IMPROVEMENTS ARE COMPLETE. SMOOTH AND REVEGETATE ALL DISTURBED AREAS. 13. ALL SWALES AND DRAINAGE STRUCTURES WILL BE CONSTRUCTED AND STABILIZED PRIOR TO HAVING RUNOFF DIRECTED TO THEM.

14. FINISH PAVING ALL ROADWAYS/DRIVEWAYS. 15. LOT DISTURBANCE OTHER THAN THAT SHOWN ON THE APPROVED PLANS SHALL NOT COMMENCE UNTIL THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.



1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 1 TO 2 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.

3. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES. 4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICH EVER IS GREATER. 5. GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.

6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL. A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE. 7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF

SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED

STABILIZED CONSTRUCTION ENTRANCE

WINTER MAINTENANCE

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH, SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE/PHOTODEGRADABLE "JUTE MATTING" (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER NOVEMBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

PRIOR TO NOV. 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO REMAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REDUCE ROADWAY EROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304.3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER NOVEMBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT WILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

SEEDING SPECIFICATIONS

1. GRADING AND SHAPING

A. SLOPES SHALL NOT BE STEEPER THAN 2:1;3:1 SLOPES OR FLATTER ARE PREFERRED. WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.

2. SEEDBED PREPARATION

A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.

B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE FEASIBLE. THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE A SEEDBED AND MIX FERTILIZER AND LIME INTO THE SOIL. THE SEEDBED SHOULD BE LEFT IN REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL.

3. ESTABLISHING A STAND

A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEDING AND INCORPORATED INTO THE SOIL KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT AVAILABLE, THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:

AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100 LBS PER 1,000 SQ. FT..

NITROGEN(N), 50 LBS PER ACRE OR 1. 1 LBS PER 1,000 SQ.FT.

PHOSPHATE(P205), 100 LBS PER ACRE OR 2. 2 LBS PER 1,000 SQ.FT.

POTASH(K20), 100 LBS PER ACRE OR 2. 2 LBS PER 1,000 SQ.FT.

(NOTE: THIS IS THE EQUIVALENT OF 500 LBS PER ACRE OF 10-20-20 FERTILIZER OR 1,000 LBS PER ACRE OF B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE

BROADCASTING, DRILLING AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS. BY CULTIPACKING OR RAKING. C. REFER TO TABLE(G-E1 THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-E1 THIS SHEET)

FOR RATES OF SEEDING. ALL LEGUMES (CROWN VETCH, BIRDS FOOT TREFOIL, AND FLAT PEA) MUST BE INOCULATED WITH THEIR SPECIFIC INOCULANT.

D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1

4. MULCH

A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING.

B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90 LBS PER 1000 SQ. FT.

5. MAINTENANCE TO ESTABLISH A STAND

A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH. B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.


C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL

MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

KEY STONE INTO CHANNEL BANKS AND EXTEND BEYOND ABUTMENTS A MINIMUM OF 18" TO PREVENT FLOW AROUND THE DAM. L= THE DISTANCE SUCH THAT POINTS A AND B ARE OF EQUAL ELEVATION. SPACING BETWEEN STRUCTURES

TEMPORARY GRADE STABILIZATION STRUCTURES SHOULD BE CHECKED AFTER EACH RAINFALL AND AT LEAS' DAILY DURING PROLONGED STORMS. ANY NECESSARY REPAIRS SHOULD BE MADE IMMEDIATELY. PARTICULAR ATTENTION SHOULD BE GIVEN TO END RUN AND EROSION AT THE DOWNSTREAM TOE OF THE STRUCTURE. WHEN THE STRUCTURES ARE REMOVED, THE DISTURBED PORTION SHOULD BE BROUGHT TO THE EXISTING CHANNEL GRADE AND THE AREAS PREPARED, SEEDED AND MULCHED. WHILE THIS PRACTICE IS NOT INTENDED TO BE USED PRIMARILY FOR SEDIMENT TRAPPING, SOME SEDIMENT WILL ACCUMULATE BEHIND THE STRUCTURES. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURES WHEN IT HAS ACCUMULATED TO ONE HALF OF THE ORIGINAL HEIGHT OF THE STRUCTURE

AFTER VEGETATION HAS STABILIZED, THESE TEMPORARY STRUCTURES SHALL BE REMOVED WITH SPECIAL CARE AS TO AVOID DISTURBING ANY UNDERLYING EROSION CONTROL FABRIC AND/OR EXISTING VEGETATION TEMPURARY STUNE CHECK DAM



CONSTRUCTION SPECIFICATIONS 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8". 2. THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 10' APART, AND DRIVEN A MINIMUM OF 16" INTO THE GROUND.

3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM


4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF. 5. PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE. 6. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED

MAINTENANCE 1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE IMMEDIATELY. 2. IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING

THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY. 3. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE 4. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN

REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

SEEDING GUIDE




NOTE: TEMPORARY SEED MIX FOR STABILIZATION OF TURF SHALL BE WINTER RYE OR DATS AT A RATE OF 2.5 LBS. PER 1000 S.F. AND SHALL BE PLACED PRIOR TO OCT. 15, IF PERMANENT SEEDING NOT YET COMPLETE.

PREPARED FOR:

ONE HOME BUILDERS, LLC PO BOX 334 STRATHAM, N.H. 03885

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



Erosion Control Mix Berm

	SEEDING RATES					
	MIXTURE	POUNDS PER ACRE	POUNDS PER 1.000 Sq. Ft.			
	A. TALL FESCUE CREEPING RED FESCUE RED TOP TOTAL	20 20 2 42	0.45 0.45 <u>0.05</u> 0.95			
	B. TALL FESCUE CREEPING RED FESCUE CROWN VETCH OR	15 10 15	0.35 0.25 0.35			
	FLAT PEA TOTAL	30 40 OR 55	0.75 0.95 OR 1.35			
*	C. TALL FESCUE CREEPING RED FESCUE BIRDS FOOT TREFOIL TOTAL	20 20 <u>8</u> 48	0.45 0.45 0.20 1.10			
	D. TALL FESCUE FLAT PEA TOTAL	20 <u>30</u> 50	0.45 0.75 1.20			
	E. CREEPING RED FESCUE 1/ KENTUCKY BLUEGRASS 1/ TOTAL	50 50 100	1.15 1.15 2.30			
	F. TALL FESCUE 1	150	3.60			
	1/ FOR HEAVY USE ATHLETIC FIELD NEW HAMPSHIRE COOPERATIVE EXCURRENT VARIETIES AND SEEDING	TENSION TURF S				

REVISIONS: DATE:

EROSION CONTROL DETAILS

PLAN FOR: RESIDENTIAL DEVELOPMENT LONG HILL ROAD MADBURY, NH

DATE: MARCH, 2014	SCALE: NTS	
PROJ. N0: NH-767	SHEET NO. 10 OF 10	