

TABLE OF CONTENTS: NON-RESIDENTIAL SITE PLAN REVIEW SHEET 1 ~ NEIGHBORHOOD PLAN BERRY SURVEYING & ENGINEERING HAS PREPARED AN INSPECTION & SHEET 2 ~ EXISTING CONDITIONS PLAN MAINTENANCE MANUAL AS PART OF THIS PROJECTS DOCUMENTATION. SHEET 3 ~ SITE SPECIFIC SOILS MAP FORALL USERS ARE BOUND TO THIS DOCUMENT AS PART OF THE SHEET 4 ~ EXISTING SHORELAND ZONE DISTURBANCE SINCE 2008 SHEET 5 ~ SURVEY LOCATED DISTURBANCE SINCE 2011 APPROVAL OF THE PLANNING BOARD. COPIES OF THE YEARLY SHEET 6 ~ SITE PLAN INSPECTIONS ARE TO BE DELIVERED TO THE TOWN OF MADBURY SHEET 7 ~ SHORELAND ZONE PLAN CHARLES STREET HOLDING, LLC PLANNING DEPARTMENT. SHEET 8 ~ PROJECT DISTURBANCE PLAN (2021) SHEET 9 ~ GRADING & DRAINAGE PLAN SHEET 10 ~ GRAVEL WETLAND #101 / P-101 SHEET 11 ~ EROSION & SEDIMENT CONTROL PLAN & 284 KNOX MARSH, LLC APPROVED MADBURY, NEW HAMPSHIRE SHEET 12 ~ LANDSCAPING PLAN PLANNING BOARD SHEET 13 ~ E101-EROSION & SEDIMENT CONTROL DETAILS SHEET 14 ~ E102-EROSION & SEDIMENT CONTROL DETAILS N.H. ROUTE 155 CHAIRPERSON SHEET 15 ~ C101-CONSTRUCTION DETAILS SHEET 16 ~ D101 DRAINAGE DETAILS SHEET 17 ~ L101-LANDSCAPING DETAILS 282 & 284 KNOX MARSH ROAD MADBURY, N.H. TAX MAP 9, LOTS 3 & 4 OWNER & APPLICANT: CHARLES STREET HOLDING, LLC SURVEYOR OF RECORD: KENNETH A. BERRY, PE, LLS STABLE GROWTH ENVIRONMENTAL, LLC WETLAND SCIENTIST: 282 KNOX MARSH ROAD CPSWQ, CPESC, CESSWI MICHAEL L. PARSONT, CWS, CPESC MADBURY, NH 03823 BERRY SURVEYING & ENGINEERING P.O. BOX 155 335 SECOND CROWN POINT ROAD DOVER, NH 03821 284 KNOX MARSH, LLC BARRINGTON, NH 03825 (603) 767-8633 284 KNOX MARSH ROAD (603) 332-2863 MADBURY, NH 03823 SOIL SCIENTIST: STABLE GROWTH ENVIRONMENTAL, LLC ENGINEER OF RECORD: KENNETH A. BERRY, PE. LLS JOHN P. HAYES III, CWS, CSS VICINITY SKETCH CPSWQ, CPESC, CESSWI P.O. BOX 155 MADBURY & DOVER, NH BERRY SURVEYING & ENGINEERING DOVER, NH 03821 SCALE:  $1" = 300' \pm$ 335 SECOND CROWN POINT ROAD (603) 767-8633 BARRINGTON, NH 03825 (603) 332-2863X M LOCATION PLAN MADBURY, NH/ DOVER, NH NOT TO SCALE MADBURYSUBJECTPARCELSLOT 16 LOT 2A TAX MAP MARSH ROAD LOT 4 - SUBJECT *PARCELS* -BELLAMYRIVERWHETHER OR NOT OTHERWISE EXPRESSLY RECITED ON THIS SITE PLAN, THE SITE PLAN APPROVAL GRANTED IS CONDITIONED ON FAITHFUL AND DILIGENT ADHERENCE REQUIRED PERMITS: BY THE OWNER/SUBDIVIDER/DEVELOPER OF ALL TERMS, CONDITIONS, PROVISIONS GENERAL PLAN SET NOTES: AND SPECIFICATIONS OF THE TOWN OF MADBURY NON-RESIDENTIAL SITE PLAN 1.) EPA NOTICE OF INTENT: PENDING REGULATIONS AS AMENDED OR AS MAY LATER BE AMENDED, IN EFFECT ON THE 1.) 11x17" PLANS ARE HALF THE PUBLISHED SCALE. DATE OF APPROVAL, UNLESS OR EXCEPT INSOFAR AS EXPRESSLY WAIVED, IN ANY 2.) NHDES SHORELAND IMPACT PERMIT: PENDING PARTICULAR, BELOW. NON - ADHERENCE MAY RESULT IN A REVOCATION OF 2.) ALL PLANS ARE CONSIDERED TO BE NOT FOR CONSTRUCTION UNLESS THEY APPROVAL. ANY VARIATION FROM THE APPROVED PLAN WILL REQUIRE A CONTAIN THE APPROVAL STAMP OF THE TOWN OF MADBURY. 3.) NATURAL HERITAGE BUREAU: NHB20-1618 RESUBMISSION FOR SITE PLAN APPROVAL.



EX	ISTING LEGEND:	PROPOSED LEGEND:			
	PERIMETER BOUNDARY COMMON PROPERTY LINE NRCS SOIL DELINEATION LINE BUILDING SETBACK LINE GRAVEL SURFACE		OUTLET STRUCTURE SIGNAGE CHECK DAM-MATERIAL AS SPECIFIED FLOW ARROW		
	POORLY / SOMEWHAT POORLY DRAINED SOIL LINE POORLY DRAINED ROADSIDE SWALE 25'/50' WET AREA BUFFER/SETBACK BUILDING AND SEPTIC SETBACK		TEMPORARY BENCH MARK (T.B.M.)		
——————————————————————————————————————	FLOOD LINE (ZONE A)  OVERHEAD UTILITIES LINE  CONTOUR LINE, MINOR  CONTOUR LINE, MAJOR	(E101) E6	DETAIL SHEET / DETAIL		
250 NHDES	EXISTING DRAIN LINE GUARD RAIL 250' NHDES SHORELAND ZONE 150' NHDES SHORELAND ZONE 50' NHDES SHORELAND ZONE LIMIT OF 2020 DISTURBANCE	F40  F40	CONTOUR MINOR CONTOUR MAJOR CULVERT W/ FLARED END SECTION (F.E.S.) PROPOSED TREE LINE GUARD RAIL SHOULDER		
0	IRON BOUND ~FND~ NHHD BOUND ~FND~		CENTER LINE CLEAR ZONE LINE BUILDING SETBACK LINE		
<u>~</u>	UTILITY POLE SINGLE SIGN POST TEST PIT		UNDER DRAIN SILT FENCE / EROSION MIX BERM FILTREXX 8" — 12" SILT SOXX AS SPECIFIED		
	CATCH BASIN W/ STRUCTURE		ORANGE CONSTRUCTION PERIMETER FENCE NRCS SOIL DELINEATION		
LrA S.C.R.D. TYP. FND	MATERIAL STOCKPILE BINS  NRCS SOIL LABEL STRAFFORD COUNTY REGISTRY OF DEEDS TYPICAL FOUND	Gs B	SOIL TYPE  RIP RAP  SUBSURFACE GRAVEL WETLAND		
			BERM		

SIGN ID NUMBE	R SIGN SIZE (MDTH x HEIGHT)	SIGN	TEXT DIMENSIONS	NO. OF SIGNS	BACKGROUND	LEGEND	BORDER	POST SIZE & QUANTITY
R1-1	30"×30"	STOP	SEE STANDARD HIGHWAY SIGNS 2004 EDITION PUBLISHED BY USDOT — FHWA	2	RED	WHITE	WHITE	SQUARE (2)
R7-8	12"x18"	RESERVED PARKING	SEE STANDARD HIGHWAY SIGNS 2004 EDITION PUBLISHED BY USDOT — FHWA	1	WHITE	GREEN W/ WHITE SYMBOL ON BLUE	RED	SQUARE (1)
R7-8a	12"x6"	VAN ACCESSIBLE	SEE STANDARD HIGHWAY SIGNS 2004 EDITION PUBLISHED BY USDOT — FHWA	1	WHITE	GREEN	GREEN	SQUARE (0)





N/F STATE OF NEW HAMPSHIRE DIV. OF PUBLIC WORKS & HGWYS CONCORD ROAD DURHAM, NH 03824 TAX MAP 3, LOT 49



SHEET 1 OF 17


KENNETH







SHEET 3 OF 17


1 inch = 50 ft.























SHEET 11 OF 17

#### NOTES: CALL DIG SAFE PRIOR TO BEGINNING WORK. (1-888-344-7233). THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF UNDERGROUND UTILITIES AND SHALL VERIFY THE EXISTENCE AND LOCATION OF THE SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAVING, WALKS, CURBING, ETC DAMAGED IN PERFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER OR GENERAL CONTRACTOR. CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL SITE CONDITIONS PRIOR TO CONSTRUCTION BIDDING. THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON THE DRAWINGS. VARIATIONS IN QUANTITIES ARE TO BE APPROVED BY THE DESIGN ENGINEER. 4. PROVIDED SMOOTH TRANSITION WHERE NEW WORK MEETS EXISTING CONDITIONS. ALL PLANT MATERIAL INSTALLED SHALL MEET THE SPECIFICATIONS OF "AMERICAN STANDARD FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN ALL PLANT MATERIALS SHALL BE FREE FROM INSECTS AND DISEASE. ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE FROM OWNER. ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REQUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING TREES AND SHRUBS THAT COULD BE IMPACTED BY THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIPMENT. CONSTRUCTION MATERIALS. SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF

10. NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT

T 503-491-2322

TREES OR TWENTY FEET WHICH EVER IS GREATER.

INCLUDE FERTILIZATION AND MULCHING AS REQUIRED.

- 12. WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERLITE BY VOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL-ROTTED OR DEHYDRATED MANURE OR COMPOST, ROTOTILL BEDS TO A DEPTH OF 8 INCHES.
- 13. MAINTENANCE OF NEW PLANTINGS AND LAWNS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND OR LANDSCAPE SUBCONTRACTOR UNTIL ACCEPTANCE BY THE OWNER. RESPONSIBILITIES SHALL INCLUDE WATERING WEEDING AND MOWING AS NECESSARY. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE, REPLACEMENT MATERIAL SHALL BE GUARANTEED FOR AND ADDITIONAL YEAR FROM TIME OF INSTALLATION.
- 14. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- 15. THE GENERAL CONTRACTOR AND OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL THREE GUYING MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MINIMUM OF ONE GROWING SEASON). ALL TEMPORARY EROSION CONTROL MEASURE SHALL BE REMOVED ONCE STABILIZATION OF DISTURBANCE HAS BEEN ACCEPTED BY OWNER.
- 16. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWINGS FOR ALL TURF AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURF IS REQUIRED FOR ACCEPTANCE.
- 17. ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
- 18. SHRUBS OR TREES WHICH DIE SHALL BE REPLACED WITHIN ONE GROWING SEASON WITH NEW SHRUBS OR TREES TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE LANDSCAPING REQUIREMENTS.
- 19. ALL REQUIRED LANDSCAPING SHALL BE INSTALLED BEFORE OCCUPANCY, OR WITHIN SIX MONTHS IF OCCUPANCY OCCURS DURING WINTER CONDITIONS.
- 20. TREES ARE TO BE 6' TALL AT PLANTING.
- 21. ALL PLANT STOCK SHALL CONFORM TO ANSI Z260.1 NURSERY STOCK, LATEST EDITIONS (AMERICAN ASSOCIATION OF NURSERYMEN, INC.)

- SHALL BE APPLIED TO ALL SHRUB AND GROUND COVER BEDS. INSTALL WEED BARRIER AS PER MANUFACTURERS RECOMMENDATIONS.
- 23. PLANT-PIT BACK-FILL SHALL BE MIXED AT A RATE OF 7 PARTS OF TOPSOIL TO 2 PARTS OF DEHYDRATED COW MANURE. SLOW RELEASE FERTILIZER SHALL BE APPLIED AS PER MANUFACTURERS RECOMMENDATIONS. USE EXISTING ON-SITE TOPSOIL AS PART OF BACK FILL WHEN AVAILABLE.
- 24. ALL LANDSCAPED AREAS NOT PLANTED WITH TREES, SHRUBS OR GROUNDCOVER SHALL BE RESTORED WITH SEED OR SOD AS INDICATED ON PLANS.
- 25. TOPSOIL WILL BE TESTED FOR FERTILIZATION REQUIREMENTS. AND SLOW RELEASE ENVIRONMENTALLY FRIENDLY FERTILIZER WILL BE APPLIED AT THE RECOMMENDED RATES.
- 26. ALL DISTURBED WETLAND BUFFER AREAS, EXCEPT FOR AREAS THAT ARE PART OF THE DRAINAGE SYSTEM, ARE TO BE RESEEDED WITH A CONSERVATION SEED MIX AND ONLY MOWED TWICE PER YEAR.
- 27. ALL PLANT SUBSTITUTIONS MUST BE APPROVED BY THE ENGINEER.
- 28. PLANTS SHALL BE SUBJECT TO INSPECTION AND APPROVAL AT THE PLACE OF GROWTH, UPON DELIVERY OR AT THE JOB SITE WHILE WORK IS ONGOING TO CONFORMITY TO SPECIFIED QUALITY, SIZE AND VARIETY.
- 29. PLANTS FURNISHED IN CONTAINERS SHALL HAVE THE ROOTS WELL ESTABLISHED IN THE SOIL MASS AND SHALL HAVE AT LEAST ONE (1) GROWING SEASON. ROOT-BOUND PLANTS OR INADEQUATELY SIZED CONTAINERS TO SUPPORT THE PLANT MAY BE DEEMED UNACCEPTABLE.
- 30. ALL PLANTS SHALL BE GUARANTEED BY THE CONTRACTOR FOR NO LESS THAN ONE FULL YEAR FROM THE TIME OF INSTALLATION. DURING THIS TIME, THE OWNER SHALL MAINTAIN ALL PLANT MATERIALS IN THE ABOVE MANNER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE PLANTS TO ENSURE PROPER CARE. IF THE CONTRACTOR IS DISSATISFIED WITH THE CARE GIVEN, HE SHALL IMMEDIATELY, AND IN SUFFICIENT TIME TO PERMIT THE CONDITION TO BE RECTIFIED, NOTIFY THE OWNER IN WRITING OR OTHERWISE FORFEIT HIS
- 31. BY THE END OF THE GUARANTEE PERIOD, THE CONTRACTOR SHALL HAVE REPLACED ANY PLANT MATERIAL THAT IS MISSING, NOT TRUE TO SIZE AS SPECIFIED, THAT HAS DIED, THAT HAS LOST NATURAL SHAPE DUE TO DEAD BRANCHES, EXCESS PRUNING OR INADEQUATE OR IMPROPER CARE, OR IS, IN THE OPINION OF THE OWNER, IN UNHEALTHY OR UNSIGHTLY CONDITION.

#### PLANTING NOTES

1. CONTRACTOR SHALL OBTAIN APPROVAL FROM L.A. PRIOR TO PURCHASING &/OR INSTALLING SUBSTITUTE PLANT MATERIAL PRIOR TO PURCHASE OF ANY SUBSTITUTE MATERIALS.

2. CONSTRUCTION ACCESS WILL BE AS DIRECTED BY L.A. CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ACCESS ROUTE AND ALL AREAS DISTURBED BY PLANTING OPERATIONS UPON COMPLETION OF CONSTRUCTION OPERATIONS, AT NO ADDITIONAL COST TO THE OWNER.

3. LAYOUT OF ALL PLANTING BEDS AND LOCATION OF PLANTS TO BE APPROVED BY L.A. ON SITE PRIOR TO CONSTRUCTION AND INSTALLATION.

4. CONTRACTOR TO REMOVE ALL DEBRIS GENERATED BY PLANT INSTALLATION. DEBRIS TO BE DISPOSED OF IN A LEGAL MANNER.

5. ALL PLANT MATERIAL SHALL BE GUARANTEED TO BE IN GOOD, HEALTHY & FLOURISHING CONDITION FOR ONE YEAR FROM THE DATE OF FINAL INSTALLATION APPROVAL BY L.A. CONTRACTOR SHALL REPLACE, WITHOUT COST TO OWNER, AND AS SOON AS WEATHER CONDITIONS PERMIT, ALL DEAD AND NON-FLOURISHING PLANTS AS DETERMINED BY THE L.A. REPLACEMENT PLANTS SHALL BE BE GUARANTEED IDENTICALLY TO ORIGINAL PLANTS, TIME PERIOD COMMENCING FROM DATE OF REPLACEMENT PLANTING APPROVAL BY L.A.

6. ALL BEDS TO BE MULCHED WITH 3" DEPTH SHREDDED BARK MULCH UNLESS NOTED OTHERWISE.

7. CONTRACTOR TO PROVIDE NECESSARY TEMPORARY IRRIGATION IF NEEDED BASED ON TIME OF YEAR THE PROJECT IS IMPLEMENTED.

8. ALL PLANT MATERIAL TO COMPLY WITH THE CITY OF DOVER'S SITE REVIEW REGULATIONS, 149-14(G), SUCH THAT THERE SHALL BE DECIDUOUS SHADE TREES PLANTED 40 FEET O.C. ALONG THE PERIMTERE OF THE PARKING LOTS AND SHRUBS PLANTED 5 FEET O.C. WITHIN THE PERIMETER BUFFER. SEE PLANT LIST FOR SPECIES AND SIZE OF

#### TEMPORARY WATERING NOTES


Vaccinium corymbosu / Highbush blueberry

2-3' B&B


1. CONTRACTOR IS RESPONSIBLE FOR MAKING SURE ALL PLANT MATERIAL HAS ADEQUATE WATER DURING THE ESTABLISHMENT PERIOD.

2. THE USE OF GATOR BAGS, SOAKER HOSE, HAND WATERING AND OTHER TECHNIQUES SHOULD BE USED TO ASSURE PROPER HYDRATION OF THE PLANTINGS IS MAINTAINED.


3. TEMPORARY IRRIGATION SYSTEMS CAN BE SET UP TO ASSIST IN WATERING ACTIVITIES.




ES T



SHEET 12 OF 17





- 4. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 5. MAINTENANCE: THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND THE DESIGN CONDITIONS HAVE NOT CHANGED. ANY DETRIMENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED. IF STONE REMOVAL HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED.
- 6 REFERENCE IS MADE TO NHDES SWM VOL. 2, 4-6, STONE BERM LEVEL SPREADERS, PAGE 162 STONE BERM LEVEL SPREADER

NOT TO SCALE

BASE WIDTH EXISTING EARTH OR FILL 4" (MIN.) LOAM, SOD

GRASS TREATMENT SWALE NOT TO SCALE


INSPECT ANNUALLY FOR EROSION, SEDIMENT ACCUMULATIONS, VEGETATION LOSS, & INVASIVE SPECIES. REPAIR AS NECESSARY.

MOW GRASS ANNUALLY TO A DEPTH OF 4".

INSTALL STABILIZATION MATTING DURING CONSTRUCATION

E3

TO BE CONSTRUCTED IAW NH SWM #2 CHAPTER 4, #5 TREATMENT SWALES, PAGE 123.




CONSTRUCTION SAFETY FENCE

NOT TO SCALE

**LEGEND** 


1. ALL SENSITIVE AREAS SHALL BE PROTECTED AS PER PLAN.
2. ALL TREES IN THE CONSTRUCTION AREA NOT SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE PRESERVED AND PROTECTED WITH HIGH VISIBILITY FENCE AS PER PLAN.
3. WHEN PRACTICABLE, INSTALL HIGH VISIBILITY 3 FEET OUTSIDE OF THE DRIP LINE OF THE TREE. SAFETY FENCE SHOULD BE EASTENED SECURELY TO THE T-POST 5. THE FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION; ANY CHANGE OF THE PROTECTIVE FENCING MUST BE APPROVED.



- THE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS POSSIBLE.
- THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%. SUBJECT TO (E), BELOW, THE MIX SHALL HAVE AN ORGANIC PORTION BETWEEN 80 AND 100%, DRY WEIGHT BASIS, AND BE FIBROUS AND ELONGATED SUCH AS FROM SHREDDED
- BARK, STUMP GRINDINGS, COMPOSED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS ORGANIC MATERIAL. THE MIX SHALL NOT CONTAIN SILTS, CLAY, OR FINE SANDS.
- THE MIX SHALL HAVE A PARTICLE SIZE BY WEIGHT OF 70 TO 85% PASSING A 6-INCH SCREEN AND A MAXIMUM OF 85% PASSING THE 0.75-INCH SCREEN. THE MIX PH SHALL BE BETWEEN 5.0 AND 8.0.
- THE BERM SHALL BE AT LEAST 12 INCHES HIGH AND AT LEAST 2 FEET WIDE. TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, EROSION CONTROL MIX BERMS, PAGE 106.

2"X2"X36" WOODEN STAKES

# - CONCRETE BLOCK



## <u>MAINTENANCE</u>

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURE OR VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY

## BLOCK & GRAVEL DROP INLET SEDIMENT FILTER NOT TO SCALE

TO BE USED IN ALL AREAS WHERE THERE WILL BE NO TRAFFIC.


## TEMPORARY EROSION CONTROL MEASURES

THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.

- EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER.
- ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN ONE POUND OF SEED PER 50 SQUARE YARDS OF AREA. (SEE SEED SPECIFICATIONS THIS SHEET)
- ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 45 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, (217,800 Sq. Ft.) WILL BE DISTURBED.
- SILT FENCES AND PERIMETER BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.
- AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED
- PER THE EPA CGP REQUIREMENTS THERE WILL BE REPORTS OF THE EROSION CONTROL INSPECTIONS IAW SWPPP PREPARED BY BS&E. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25" OR GREATER RAIN EVENT.
- 8. DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- 9. DO NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION
- 10. DRIVEWAYS AND CUT AND FILL SPLOPES MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINAL GRADE.
- 11. STABILIZATION MEANS:
- 11.1. A MINIMUM OF 85% OF VEGETATIVE COVER HAS BEEN ESTABLISHED. 11.2. A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN
- INSTALLED, OR 11.3. EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.
- 12. THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

13. THE NHDES STORMWATER MANUAL, IN THREE VOLUMES, DATED DECEMBER 2008, IS A PART OF THIS PLAN SET AND THE MORE RESTRICTIVE WILL GOVERN. (NH SWM)

# E11



RECOMMENDED MAINTENANCE SCHEDULE -EACH SILTSACK SHOULD BE INSPECTED AFTER EVERY MAJOR RAIN EVENT, AND MUST BE MAINTAINED.

-IF THERE HAVE BEEN NO MAJOR EVENTS, SILTSACK SHOULD BE INSPECTED EVERY 2-3 WEEKS.

-THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF CORD IS COVERED WITH SEDIMENT, THE SILTSACK SHOULD BE EMPTIED.

-TO BE USED IN ALL AREAS WHERE THERE WILL BE - ARE SUBJECT TO DAMAGE BY SNOW PLOWS, AND

MUST BE INSPECTED AFTER ANY SNOW EVENT AND REPLACED AS REQUIRED. TO BE CONSTRUCTED IAW NH SWM #3 4-2


SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118

SILTSACK DETAIL NOT TO SCALE

CROWN POINT O3825 (603)  $\mathbf{m}$ OF NEW HAN

Σ×

H(



E-101

PLACED 10' O.C. E10(SEE SECTION) FILTREXX SOXX (12" TYPICAL) AREA TO BE PROTECTED WATER FLOW

NOTE: KEY STONE INTO CHANNEL BANKS AND EXTEND IT BEYOND TH ABUTMENTS A MINIUM OF 18" TO PREVENT FLOW AROUND THE DAM. WORK AREA  $\underline{PLAN}$  not to scale

ANGULAR STONE 8.0'

STONE GRADE STABILIZATION STRUCTURE

~SILTFENCE

WOVEN WIRE FENCE WY PROPEX-SILT STOP

OR APPROVED EQUAL

-SILTFENCE TO BE EMBEDDED

PAVEMENT

NOT TO SCALE

INTO THE GROUND A MIN. OF 6"

SEDIMENT CONTROL FABRIC

,6" MIN. DEPTH & HORIZONTAL

ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS. FILTER MEDIA FILL TO MEET APPLICATION REQUIRMENTS. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER. SILTSOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT

SILTSOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIRMENTS OF THE SPECIFIC APPLICATION. FILTREXX SOXX IS A REGISTERED TRADEMARK OF FILTREXXIN TERNATIONAL, LLC. SILT FENCE IS NOT A SUBSTITUTION FOR SILT SOXX AND ANY EQUAL SUBSTITUTION TO BE APPROVED.

TO BE CONSTRUCTED IAW FILTREXX, SECTION 1: EROSION & SEDIMENT CONTROL (PAGE 323) - CONSTRUCTION ACTIVITIES, SWPPP CUT SHEET: FILTREXX SEDIMENT CONTROL

CONTROLNOT TO SCALE 2"X2"X36" WOODEN STAKES PLACED 10' O.C. — FILTREXX SOXX (8" OR 12" SILT FENCE-BLOWN/PLACED FILTER MEDIA -ÀS NOTED) AREA TO BE PROTECTED WORK AREA

Filtrexx International, LLC 35481 Grafton Eastern Rd | Grafton, Oh 44044 440-926-2607 | fax: 440-926-4021 WWW.FILTREXX.COM OR APPROVED EQUAL

O BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT


CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET

PROTECTION, PAGE 118.

FILTREXX SEDIMENT

NOTE: FOR AREAS REQUIRING DOUBLE PERIMETER CONTROL WITHIN 50' OF JURISDICTIONAL WETLANDS AND NOT FOR ALL SILT SOXX APPLICATIONS. THIS DUPLICATION MAY BE SPECIFIED AS 12" SILT SOXX OR ORANGE CONSTRUCTION FENCE AS NOTED.

 $\underline{SECTION}$  not to scale



RECCOMEND USE OF HAY BALES FOR EROSION

CONTROL.

#### PIPE OUTLET PROTECTION CONSTRUCTION SPECIFICATIONS

- 1. THE SUB GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS. SPECIFIED GRADATION.
- 2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO NHDOT SECTION 583.
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- 4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.
- 5. TO BE CONSTRUCTED IAW NH SWM #2 4-6 CONVEYANCE PRACTICES, 6. OUTLET PROTECTION, PAGE 172.

# E 14

TABLE	7-24-	-RECOMMENDE	D RIP I	RAP GRADA	TION RANGE
d50 SI	ZE=	0.5	FEET	6	INCHES
		SMALLER EN d50 SIZE		ZE OF STO	NE (INCHES) TO
	100%		9		12
	85%		8		11
50%			6		9
	15%		2		3

## CONSTRUCTION SEQUENCE:

- 1.) CUT AND REMOVE TREES IN CONSTRUCTION AREA ONLY AS REQUIRED, RELOCATE ANY PROJECT T.B.M.
- 2.) CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMENT EROSION AND DETENTION CONTROL FACILITIES AS SPECIFIED. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SOIL LAND DISTURBANCE AND MUST BE REVIEWED AND APPROVED BY THE COMMUNITY SERVICES DEPARTMENT.
- 3.) EROSION, SEDIMENT AND DETENTION CONTROL FACILITY SHALL BE INSTALLED & STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM. TEMPORARY DIVERSIONS MAY BE REQUIRED. POST CONSTRUCTION STORM WATER MANAGEMENT PRACTICES MUST BE INITIATED AND STABILIZED EARLY IN THE PROCESS.
- 4.) CLEAR, CUT AND DISPOSE OF DEBRIS IN APPROVED FACILITY
- 5.) CONSTRUCT TEMPORARY CULVERTS AS REQUIRED, OR DIRECTED
- 6.) CONSTRUCT ROADWAYS FOR ACCESS TO DESIRED CONSTRUCTION AREAS. ALL ROADS SHALL BE STABILIZED IMMEDIATELY
- 7.) START BUILDING CONSTRUCTION
- 8.) INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. INSTALL RAIN GARDENS. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING.
- 9.) BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AS REQUIRED, OR DIRECTED. NO AREA IS ALLOWED TO BE DISTURBED FOR A LENGTH OF TIME THAT EXCEEDS 60 DAYS BEFORE BEING STABILIZED. DAILY, OR AS REQUIRED. ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADES. ALL CUT AND FILL SLOPES SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADES.
- 10.) CONSTRUCT TEMPORARY BERMS, DRAINS DITCHES, SILT FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 11.) INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION. ALL SWPPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFIED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER (PE), A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC), A CERTIFIED EROSION SEDIMENT AND STORM WATER INSPECTOR (CESSWI), OR A CERTIFIED PROFESSIONAL IN STORM WATER QUALITY (CPSWQ). INSPECTION REPORTS SHALL BE SUBMITTED TO THE COMMUNITY SERVICES DEPARTMENT.
- 12.) COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 13.) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE
- 14.) SMOOTH AND REVEGETATE ALL DISTURBED AREAS.
- 15.) FINISH PAVING ALL ROADWAYS.

SECTION A-A

PIPE OUTLET TO FLAT AREA

WITH NO DEFINED CHANNEL

SEEDING GUIDE

NOTE: Temporary seed mix for stabilization

of turf shall be winter rye or oats at a

be placed prior to OCT. 15, if permanent

rate of 2.5 lbs. per 1000 s.f. and shall

seeding not yet complete.

ECREATION SITES

GRADING AND SHAPING A. SLOPES SHALL NOT BE STEEPER THAN 2:1; 3:1 SLOPES OR FLATTER ARE

GRAVEL PIT, SEE NH-PM-24 IN APPENDIX FOR RECOMMENDATION REGARDING RECLAMATION OF SAND AND GRAVEL PITS.

SEEDING SPECIFICATIONS

/ REFER TO SEEDING MIXTURES AND RATES IN TABLE 7—36. 7 POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREA AND ATHLETIC FIELDS

- WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED. SEEDBED PREPARATION
- A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS. B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE A SEED BED AND MIX FERTILIZER AND LIME INTO THE SOIL. THE SEEDBED SHOULD BE LEFT IN REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE 4. MULCH OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL.

PIPE OUTLET PROTECTION

NOT TO SCALE

NOTE: GEOTEXTILE FABRIC

OR FILTER MATERIAL TO

BE PLACED BETWEEN

SECTION A-A

3800 RELATIVE TO INVASIVE SPECIES.

PIPE OUTLET TO WELL-DEFINED CHANNEL

NOTE: THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS

THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR

TALL FESCUE CREEPING RED FESCUE RED TOP

TALL FESCUE CREEPING RED FESCUE CROWN VETCH

. TALL FESCUE 1

CONSERVATION MIX

TALL FESCUE (35%)

WHITE CLOVER (3%)

CREEPING RED FESCUE (25%) 15

PERENNIAL RYEGRASS (10%) 5

KENTUCKY BLUEGRASS (10%) 15

ANNUAL RYEGRASS (12%)

SEEDING RATES

POUNDS PER POUNDS PER PER ACRE 1,000 Sq. Ft.

30 0.75 40 OR 55 0.95 OR 1.35

POUNDS

PER ACRE 1,000 S.F.

150

RIP RAP AND SOIL.

EXCELLENT

- ESTABLISHING A STAND A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF
- AND INCORPORATED INTO THE SOIL KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT
- THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED: AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100LBS. PER 1,000 SQ.FT. NITROGEN(N), 50LBS. PER ACRE OR 1.1LBS. PER 1,000 SQ.FT. PHOSPHATE(P205), 100LBS. PER ACRE OR 2.2LBS. PER 1,000 SQ.FT. POTASH(K20), 100LBS. PER ACRE OR 2.2LBS. PER 1,000 SQ.FT.
- (NOTE: THIS IS THE EQUIVALENT OF 500LBS. PER ACRE OF 10-20-20 FERTILIZER OR 1,000LBS. PER ACRE OF 5-10-10.)

B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING. C. REFER TO TABLE(G-E1 THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-E1 THIS SHEET) FOR RATES OF SEEDING. ALL LEGUMES (CROWNVETCH, BIRDSFOOT TREFOIL, AND FLATPEA) MUST BE INOCULATED WITH THEIR SPECIFIC INOCULANT.

POUNDS PER

0.35

0.35

0.12

0.12

0.35

0.16

D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1

- A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER
- B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90LBS PER 1000 S.F.
- 5. MAINTENANCE TO ESTABLISH A STAND A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH.
- B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND
- BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED. C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.
- TO BE CONSTRUCTED IAW NH SWM #3 4-1 EROSION CONTROL PRACTICES, PERMANENT VEGETATION, PAGE 60.

ANCHOR HOOK PER

MANUFACTURER'S REQUIREMENTS

# E 18 DEFINITION OF STABLE:

PER ENV-WQ 1500 ALTERATION OF TERRAIN

- BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED. A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED. A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP-RAP HAS BEEN INSTALLED.
- 4. OR, EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

#### ADDITION STABILIZATION NOTES:

- HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL EROSION OF NEWLY GRADED AREAS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER THEIR CONSTRUCTION.
- DISTURBED SOIL AREAS SHALL BE EITHER TEMPORARILY OR PERMANENTLY STABILIZED. IN AREAS WHERE FINAL GRADING HAS NOT OCCURRED, TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN (7) CALENDAR DAYS FOR EXPOSED SOIL AREAS THAT ARE WITHIN ONE HUNDRED (100) FEET OF A SURFACE WATER BODY OR A WETLAND AND NO MORE THAN 14 CALENDAR DAYS FOR ALL OTHER AREAS. PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THREE (3) CALENDAR DAYS FOLLOWING COMPLETION OF FINAL GRADING OF EXPOSED SOIL AREAS.

### WINTER STABILIZATION NOTES

TO OCTOBER 15TH SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE 'JUTE MATTING' (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

3. PRIOR TO OCT. 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO REMAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REDUCE ROADWAY EROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304.3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.


4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT WILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH. ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

5. ENV-WQ 1505.06 COLD WEATHER SITE STABILIZATION (B)(1) LIMITS ARE OF EXPOSURE TO ONE ACRE OF UNSTABILIZED SOIL WITHOUT OBTAINING A WAIVER AND WINTER CONSTRUCTION

YIN ( INEE Poin ( . <del>S</del> Z

LAN JING 1 282 ADBU 1P 9,

35 T



SHEET 14 OF 17

E - 102

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR

4" TOPSOIL (MIN.) AND SEED TO ESTABLISH INSTALL ROLLED EROSION CONTROL BLANKET WITH ANCHOR HOOKS AS PER MANUFACTURES REQUIREMENTS. SUBMIT SHOP DRAWINGS FOR APPROVAL.

) NAG BIONET S 150 BN 3:1 TO 2:1 SLOPE ) NAG BIONET SC 150 BN 2:1 TO 1:1 SLOPE 3.) NAG BIONET SC 125 BN 1:1 AND GREATER


TO BE CONSTRUCTED IAW NH SWM #3 4-1 EROSION


OVERLAP EDGES


CONTROL PRACTICES, TEMPORARY EROSION CONTROL ANCHOR PATTERN AND INSTALLATION INSTRUCTIONS FROM NORTH AMERICAN GREEN (NAG) AND AMERICAN EROSION

COMPANY (AEC) WILL BE FOLLOWED FOR EACH APPLICATION AND SLOPE CONDITIONS WILL APPLY.

> ROLLED EROSION CONTROL BLANKET (RECB) SLOPE STABILIZATION DETAIL NOT TO SCALE









Angle Grates are designed to cover inlet orifices and prevent small to medium debris from passing through. The top angled design helps to minimize the amount of debris that settles on top after the water receeds. All grates are made from plate for a clean and smooth contact surface.

- Plate design for a clean appearance Standard 2" openings (other sizes can be made) Angled top/front plate to maximize debris deflection
- Mounting flanges on 3 sides allows grate to be mounted at floor level Galvanized steel construction. Can be made from aluminum or stainless

CONE GRATE NOT TO SCALE

MUST BE HAALA INDUSTRIES INC. OR EQUAL.




CG12TM Part No. CG12TM


> Top Mount Cone Grates are designed to mount on the top of round manhole inlet or outlet structures to keep debris from entering the storm water system. Top mount cone grates are easy to install and allow for at grade manhole installations but can be used in a variety of applications. Grates 96" and larger are made as a two piece, bolt together design.


- Plate and bar hybrid design is both clean and cost effective Made from 1/2" plate with 3/4" or 1" round bars depending on grate size Anti vortex plate can be added upon request
- Hinged and lockable access doors can be added upon request
- Galvanized steel construction. Can be made from aluminum or stainless






UNPAVED PAVED 4" TOPSOIL AND SEED (TYP) SEE PERMANENT PAVEMENT PATCH DETAIL OR TYPICAL COMMON FILL (SUITABLE MATERIAL FROM EXCAVATION) PAVEMENT SECTION DETAIL FOR PAVEMENT AND GRAVEL COVER FOR DRAIN VARIES CLEAN SAND TO MIN. 12" ABOVE TOP OF PIPE FOR HDPE PIPE. SIZE 67 TO TOP OF PIPE. -UNDISTURBED MATERIAL O.D. + 2'-0" (3'-0" MIN) PLASTIC DRAIN PIPE (HDPE) SHALL BE ADS N-12 (CORRUGATED EXTERIOR/SMOOTH INTERIOR) OR EQUAL MEETING AASHTO M-252 AND H-20 LOADING. DI DRAIN PIPE SHALL BE CL. 50.





NOT TO SCALE



1.) ENSURE DISCHARGE POINT IS STABILIZED WITH VEGETATION OR PROPER EROSION AND SEDIMENT CONTROL PRACTICES.

2.) USE DIFFUSER NOZZLE OR LOW DISCHARGE RATE TO PREVENT SCOURING. 3.) TO BE PLACED AT AN UPLAND LOCATION THAT WILL ALLOW WATER TO DRAIN

4.) SIZE OF DE-WATERING AREA TO BE 10' X 10', ADJUST SIZE DEPENDING ON VÓLUME AND USE.


5.) ADDITIONAL BALES MAY BE USED TO INCREASE RETENTION AND FILTERING.

<u>DE-WATERING BASIN</u> NOT TO SCALE

# D10


PART No.	PIPE SIZE	А	B(MAX)	Н	L	W
1510-NP	15" 375 mm	6.5" 165 mm	10" 254 mm	6.5" 165 mm	25" 635 mm	29" 735 mm
1810-NP	18" 450 mm	7.5" 190 mm	15" 380 mm	6.5" 165 mm	32" 812 mm	35" 890 mm
2410-NP	24" 600 mm	7.5" 190 mm	18" 450 mm	6.5" 165 mm	36" 900 mm	45" 1140 mm
3010-NP	30" 750 mm	10.5" 266 mm	N/A	7.0" 178 mm	53" 1345 mm	68" 1725 mm
3610-NP	36" 900 mm	10.5" 266 mm	N/A	7.0" 178 mm	53" 1345 mm	68" 1725 mm

NOTE: PE THREADED ROD W/ WING NUTS PROVIDED FOR END SECTIONS 15"-24". 30" & 36" END SECTIONS TO BE WELDED PER MANUFACTURER'S



# HEADWALL (CONCRETE)

NOT TO SCALE



1. TRAP TO BE INSTALLED AS CLOSE TO THE DISTURBED AREA OR SOURCE OF SEDIMENT AS


2. THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE TRAP SHALL BE LESS THAN 5 ACRES. 3. THE MINIMUM VOLUME OF THE TRAP SHALL BE

3,600 CUBIC FEET OF STORAGE FOR EACH ACRE OF DRAINAGE AREA. 4. THE SIDE SLOPES OF THE TRAP SHALL BE 3:1 OR FLATTER AND SHALL BE STABILIZED


IMMEDIATELY AFTER THEIR CONSTRUCTION.

5. THE OUTLET OF THE TRAP SHALL BE A MINIMUM OF ONE FOOT BELOW THE CREST OF THE TRAP AND SHALL DISCHARGE TO A STABILIZED AREA. 6. THE TRAP SHALL BE CLEANED WHEN 50 PERCENT

OF THE ORIGINAL VOLUME IS FILLED. 7. THE MATERIALS REMOVED FROM THE TRAP SHALL BE PROPERLY DISPOSED OF AND STABILIZED.



STONE LINED SEDIMENT TRAP NOT TO SCALE



	SIEVE DESIGNATION	SIZE OF STONE (INCHES)
H :RM	100%	12
IXIW	84-100%	6
	68-83%	3
	42-55%	1
	8-12%	NO. 4

FERENCE IS MADE TO A IG TERM MAINTENANCE NUAL PREPARED BY BERR URVEYING & ENGINEERING HICH IS ON FILE AT THE ITY OF MADBURY PLANNIN EPARTMENT, AND CAN BE OUND AT THE OFFICE OF BERRY SURVEYING & NGINEERING. (603)

D-101

OF NEW HAME KENNETH) BERRY No. 14/4/2 SONAL EN SHEET 16 OF 17

W A

HOI 55

